Sl No	Description	Unit	Qunty	Rate in Rupees		Amount Rs
				Figures	Words	
	labour,HOM curing complete as per specifications in cement mortar 1:4					
65	Providing and fixing unplasticised PVC Pipes of 315mm outer dia with working pressure 10kg/sq cm with perporations wrapped with Geotextiles filter fabrics ,pipe fittings,clips,marking good the floor, including cost of all materials,labour charges,HOM and testing complete as per specifications	Sqm	3.00	5009.93	Five Thousand Nine Rupees and Ninety Three Paise only.	15030
66	providing and filling the recharge pit trenches with stone with sizes of 20 & 40 mm and filler aggregates and Lime stone dust of size 0.075 mm as a top layear over Gravel , packed with stone spalls , 20mm size laid over a layer of 40mm stone aggregate and specific gravity not less than 2.65, , satisfying the requirements laid down in clause 2504.2.2. of MORTH and approved design complete as per specifications MORTH Specification No 704	Cum	20.34	2216.46	Two Thousand Two Hundred Sixteen Rupees and Fourty Six Paise only.	45083
67	Providing and laying 100mm thick pre-cast cover slabs over drains of width not exceeding 800 mm using M20 concrete reinforced with steel @ 6.00 kg/Sqm, slabs jointed in CM 1:3 proportion and nicely finished including providing	Sqm	9	1145.86	One Thousand One Hundred Forty Five Rupees and Eighty Six Paise only.	10313

Sl No	Description	Unit	Qunty	Rate in Rupees		Amount Rs
				Figures	Words	
	holes in the Cover slabs wherever necessary for easy drainage of surface water including of labour, materials, HOM, curing, lead and lift charges etc, Complete as per MORTH specifications No. 1500,1700.					
68	KSRRB M300-9. Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/sludge manure, planting the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year complete as per specifications. MORTH Specification No. 307	Each	410	1113.00	One Thousand One Hundred Thirteen Rupees only.	456330
69	Tree Transplantation, Trimming of branches with systematic method, prepration of the ball of earth with respect the age and girth at the breast height of the tree by machinery and skilled labours, digging the pits by J.C.B at Transplantating site proportionately with respect to size of ball, transporation of prepared tree by one or two CRANES as the case may be with the help of technically sound skilled labours load them techinically in truck transport to the destination, watering mixed with chemically	Each	40	19950.00	Nineteen Thousand Nine Hundred Fifty Rupees only.	917700

Sl No	Description	Unit	Qunty	Rate in Rupees	Words	Amount Rs
	prepared root reviver at one liter with 2000 liters of water till its revival, clearing the cut branches and disposal as directed by the engineer incharge. planting of tall tree saplings having wide environmental and aesthetic values having health of 8feet to 10feet at the ratio of 1:2 in the same locality and maintenance as per tree preservation Act 1976. Periodical watering and any other cultural operation required if any over a period of 8 months or till the on set of Mansoon.					
Total Amount (Rs)						44930813

Executive Engineer 18/11/2022
Roads Infrastructure Division, Yelahanka/Dasarahalli Division
Bruhat Bengaluru Mahanagara Palike
Bengaluru-92.

18/11/2022